

Section 01581

EXCAVATION IN PUBLIC WAY PERMIT SIGNS

PART 1 G E N E R A L

1.01 SECTION INCLUDES

- A. Project sign installation.
- B. Maintenance and removal of Project sign.

1.02 SYSTEM DESCRIPTION

- A. Sign Construction: Construct signs of new materials.
- B. Appearance: Maintain signs to present a clean and neat look throughout the Contract duration.
- C. Sign Placement: Place signs at each street entrance to street cut excavation.

1.03 SUBMITTALS

- A. Submit Shop Drawings under provisions of Section 01330 - Submittal Procedures.
- B. Show content, layout, lettering style, lettering size and colors. Make sign and lettering to scale, clearly indicating condensed lettering, if used.

PART 2 P R O D U C T S

2.01 SIGN LAYOUT

- A. Conform to Texas Manual on Uniform Traffic Control Devices. Minimum size: 36 inches by 36 inches.
- B. Lettering: Uppercase Helvetica Regular lettering.
- C. Composition: Include on sign copy of street cut permit, title "City of Houston", contracting department's name, address, and emergency telephone number and Contractor's name. Project Manager will provide department name, address, and emergency telephone number for preparation of sign.

**PART 3 EXECUTION**

**3.01 INSTALLATION**

- A. Install Project signs before commencement of pavement excavation in Public Way.
- B. Position sign so it is fully visible and readable to general public.
- C. Erect sign level and plumb.
- D. Erect sign so that top edge of sign is at a nominal 8 feet above existing grade.

**3.02 MAINTENANCE AND REMOVAL**

- A. Keep signs and supports clean. Repair deterioration and damage.
- B. Remove signs, framing, supports and foundations to depth of at least 2 feet upon completion of the Work. Restore area to condition equal to or better than before construction.

**END OF SECTION**